



- ① RIGID PIPE: CA-7 SHALL BE PLACED FROM 4" BELOW PIPE TO THE SPRING LINE. FLEXIBLE PIPE: CA-7 SHALL BE PLACED FROM 4" BELOW PIPE TO 1' OVER T.O.P.
- ② CA-6 OR APPROVED TRENCH BACKFILL.  
FOR NON-PAVED AREAS: SELECT EXCAVATED MATERIAL MAY BE SUBSTITUTED FOR CA-6 AS DIRECTED BY THE ENGINEER.
- ③ CONTROLLED LOW-STRENGTH MATERIAL (CLSM) I.D.O.T. APPROVED MIX WHEN REQUIRED BY CITY ENGINEER.
- ④ ALL CLSM INSTALLATIONS REQUIRE CA-7 PLACEMENT TO 1' OVER T.O.P.
- ⑤ MAXIMUM TRENCH WIDTH IN ACCORDANCE WITH SECTION 20-4.05 STANDARD SPECIFICATIONS FOR WATER & SEWER CONSTRUCTION IN ILLINOIS - CURRENT EDITION



REVISIONS	
DATE: 04-18	BY: DGoewey

SEWER TRENCH DETAIL PAVED & UNPAVED		
SCALE: NOT TO SCALE	CHECKED: LA	DRAWING NUMBER
DATE: 1/04	DRAWN: DG	EXHIBIT III-A-1