


- ① CA-7 SHALL BE PLACED 4" BELOW PIPE.
- ② CA-6 SHALL BE PLACED 1' OVER T.O.P.
- ③ CONTROLLED LOW-STRENGTH MATERIAL (CLSM) I.D.O.T. APPROVED MIX WHEN REQUIRED BY CITY ENGINEER.
- ④ CA-6 OR APPROVED TRENCH BACKFILL.  
FOR NON-PAVED AREAS: SELECT EXCAVATED MATERIAL MAY BE SUBSTITUTED FOR CA-6 AS DIRECTED BY THE ENGINEER.
- ⑤ MAXIMUM TRENCH WIDTH IN ACCORDANCE WITH SECTION 20-4.05 - STANDARD SPECIFICATIONS FOR WATER & SEWER CONSTRUCTION IN ILLINOIS CURRENT EDITION

	REVISIONS		WATER TRENCH DETAIL PAVED & UNPAVED		
	DATE: 04-18	BY: DGoewey	SCALE: NOT TO SCALE	CHECKED: LA	DRAWING NUMBER
			DATE: 1/04	DRAWN: DG	EXHIBIT III-C-1